MYSORE CITY IMPROVEMENTS TRUST BOARD.

Dated 14th May 1913.

Notice is hereby given that sealed tenders will be received at the office of the Chairman, Mysore City Improvements Trust Board, up to 30th May 1913, for restoring the collapsed portion of Col. Purchase's drain. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1913.

2. The plans, detailed estimate and conditions may be seen at the Chairman's Office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Chairman. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty only in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring the collapsed portion of Col. Purchase's drain," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Government of Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the approximate quantities for restoring the collapsed portion of Col. Purchase's drain.

No.	*Particulars*	*Per*	*Quantity*
1.	Earthwork excavation for a depth of 6 ft. 1st step ...	C. yd.	5,340
2.	Do do 6 ft. 2nd step ..	„	4,088
3.	Do do 6 ft. 3rd step ...	„	3,097
4.	Do do 6 ft. 4th step ...	„	1,536
5.	Dismantling and removing cement concrete arch ...	C. ft.	2,314
6.	Do armoured do slab ...	„	656
7.	Refilling with earth	C. yd.	14,195
8.	Dismantling and removing old brick masonry wall ...	C. ft.	6,525
9.	Do the floor of drain	S. ft.	2,393
10.	Removing slushy and miry soil	C. yd.	205
11.	Surki mortar concrete	C. ft.	4,812
12.	Table moulded bricks in cement mortar (mixture of cement mortar 1: 4)	„	11,256
13.	Cement plastering ½" thick mixture 1: 2	Sq.	83·74
14.	Constructing manholes	No.	3
15.	Bailing water	Lump sum	rupees.

T. G. LAKSHMANA RAO,
Chairman.

KADUR DIVISION.

Notification dated Camp Lakvalli, 26th March 1913.

Traffic over Kenchinbagalhalla bridge, at 6—9th mile on Tarikere-Mangalore road, is closed as the bridge is under improvement. Temporary road is available for traffic.

K. PONNAPPA,
Executive Engineer.

No. 2089, *dated 3rd—6th May* 1913.

Copies of the Mysore Registration Manual, Parts I, II and III, will be available for sale at Re. 0-6-0 per set, at the Government Central Book Depot, Fort, Bangalore, from the 15th instant.

M. KANTARAJ URS,
Inspector-General of Registration.